



U.S. Department
of Transportation
**Federal Highway
Administration**

Eastern District Federal Division

1000 North Glebe Road
Arlington, Virginia 22201

APR 19 1985

In Reply Refer To:
HPC-15

STAT

[Redacted]
New Building Project Office
Central Intelligence Agency
P.O. Box 20505
Washington, D.C. 20505

STAT

Dear [Redacted]

Enclosed for your review and comments is one copy each of the plans, Special Contract Requirements, and Engineer's Estimate for George Washington Memorial Parkway (GWMP) Project 1A58.

The project consists of pavement widening and other work for the acceleration lane from the CIA-FHWA Federal Area at Langley to northbound GWMP in Fairfax County, Virginia. It is expected to allow 40 calendar days for the contract work.

The estimated cost of the project is \$960,000 including contract, engineering, and administration cost. Please forward the funds at your earliest convenience.

We expect to negotiate this project under the Small Business Administration's 8(a) Program.

Your comments are requested by May 17, 1985.

Sincerely yours,

Roy M. Crawford
Acting Division Engineer

Enclosures

FEDERAL HIGHWAY ADMINISTRATION
 EASTERN DIRECT FEDERAL DIVISION
 ARLINGTON, VIRGINIA
 TABULATION OF BIDS

IFB DTFH 71-85-B-000XX

TABULATION OF BIDS FOR GEORGE WASHINGTON
 MEMORIAL PARKWAY, PROJECT 1A58, CONSISTING OF
 PAVEMENT WIDENING AND OTHER WORK FOR
 ACCELERATION LANE FROM CIA-FHWA FEDERAL AREA AT
 LANGLEY TO NORTHBOUND GWMP IN FAIRFAX COUNTY,
 VIRGINIA. TYPE CODE Y006.

+++++
 + ENGINEER'S +
 + ESTIMATE DATED +
 + APRIL 9, 1985 +
 +++++

FOR OFFICIAL USE ONLY

| ITEM NO. | ITEM | UNIT | QUANTITY | UNIT PRICE | AMOUNT |
|-----------|--|------|-------------|------------|-----------|
| 202(3A) | REMOVAL OF BITUMINOUS PAVEMENT(FULL DEPTH) | SQYD | 1,400.000\$ | 7.000\$ | 9,800.00 |
| 202(3F) | REMOVAL OF BITUMINOUS PAVEMENT(MILLING) | SQYD | 4,000.000 | 4.000 | 16,000.00 |
| 202(5B) | REMOVAL OF CONCRETE CURB | LNFT | 2,100.000 | 3.000 | 6,300.00 |
| 203(3) | UNCLASSIFIED EXCAVATION | CUYD | 700.000 | 20.000 | 14,000.00 |
| 204(4F) | EROSION CHECK FOR SOIL EROSION AND POLLUTION CONTROL | LNFT | 1,500.000 | 5.000 | 7,500.00 |
| 304(3F) | CRUSHED AGGREGATE BASE, GRADING B, C, OR D | TON | 1,000.000 | 20.000 | 20,000.00 |
| 403(1B) | HOT BITUMINOUS CONCRETE PAVEMENT, GRADING B | TON | 500.000 | 60.000 | 30,000.00 |
| 403(1D) | HOT BITUMINOUS CONCRETE PAVEMENT, GRADING D | TON | 700.000 | 65.000 | 45,500.00 |
| 601(1) | MOBILIZATION | LPSM | | | 71,564.00 |
| 603(21DC) | 18-INCH REINFORCED CONCRETE PIPE, CLASS III | LNFT | 30.000 | 50.000 | 1,500.00 |
| 604(2A) | INLETS, TYPE A | EACH | 2.000 | 3,000.000 | 6,000.00 |
| 604(2G) | INLETS, TYPE D1-7A | EACH | 5.000 | 3,000.000 | 15,000.00 |
| 604(6) | INLET, ADJUSTMENT | EACH | 4.000 | 850.000 | 3,400.00 |
| 604(9) | CAPPING INLET | EACH | 3.000 | 200.000 | 600.00 |

FOR OFFICIAL USE ONLY

FEDERAL HIGHWAY ADMINISTRATION
 EASTERN DIRECT FEDERAL DIVISION
 ARLINGTON, VIRGINIA
 TABULATION OF BIDS

TABULATION OF BIDS FOR GEORGE WASHINGTON
 MEMORIAL PARKWAY, PROJECT 1A58

+++++
 + ENGINEER'S +
 + ESTIMATE DATED +
 + APRIL 9, 1985 +
 +++++

| ITEM NO. | ITEM | UNIT | QUANTITY | UNIT PRICE | AMOUNT |
|----------|--|------|-----------|------------|------------|
| 604(21A) | INLET MODIFICATION, TYPE D1-7A | EACH | 5.000 | 1,200.000 | 6,000.00 |
| 605(17A) | 4-INCH-PIPE FOR UNDERDRAINS | LNFT | 1,000.000 | 14.000 | 14,000.00 |
| 609(1E) | PORTLAND CEMENT CONCRETE CURB, 16-INCH DEPTH TYPE 2 OR 3 | LNFT | 800.000 | 14.000 | 11,200.00 |
| 610(11) | STONE MASONRY GUARDWALL WITH DOUBLE MASONRY FACE | LNFT | 1,800.000 | 150.000 | 270,000.00 |
| 619(17) | LOOSE RIPRAP, CLASS II | TONS | 150.000 | 10.000 | 1,500.00 |
| 624(3A) | FURNISHING AND PLACING TOPSOIL(2-INCH DEPTH) | SGYD | 4,500.000 | 2.000 | 9,000.00 |
| 625(17) | SEEDING (WITH MULCH) | UNIT | 20.000 | 100.000 | 2,000.00 |
| 626(1) | FURNISH AND PLANT TREES AND SHRUBS | LPSM | | | 70,000.00 |
| 629(1) | SOLID SODDING | SGYD | 4,500.000 | 6.000 | 27,000.00 |
| 633(4C) | ALUMINUM SIGN PANELS TYPE III REFLECTIVE SHEETING | SGFT | 20.000 | 50.000 | 1,000.00 |
| 634(1) | TRAFFIC MARKINGS, REFLECTORIZED, BROKEN, WHITE OR YELLOW | LNFT | 3,000.000 | 0.500 | 1,500.00 |
| 634(2) | TRAFFIC MARKINGS, REFLECTORIZED, SOLID, WHITE OR YELLOW | LNFT | 4,800.000 | 0.500 | 2,400.00 |
| 635(1) | CONSTRUCTION SIGNS | SGFT | 253.000 | 12.000 | 3,036.00 |
| 635(2B) | BARRICADE, TYPE II | EACH | 100.000 | 140.000 | 14,000.00 |
| 635(2C) | BARRICADE, TYPE III | EACH | 5.000 | 300.000 | 1,500.00 |

FOR OFFICIAL USE ONLY

FEDERAL HIGHWAY ADMINISTRATION
 EASTERN DIRECT FEDERAL DIVISION
 ARLINGTON, VIRGINIA
 TABULATION OF BIDS

TABULATION OF BIDS FOR GEORGE WASHINGTON
 MEMORIAL PARKWAY, PROJECT 1A58

+++++
 + ENGINEER'S +
 + ESTIMATE DATED +
 + APRIL 9, 1985 +
 +++++

| ITEM NO. | ITEM | UNIT | QUANTITY | UNIT PRICE | AMOUNT |
|----------|--|-------|-----------|------------|------------|
| 635(6A) | CONE, TYPE A | EACH | 100.000 | 40.000 | 4,000.00 |
| 635(12) | TEMPORARY CONCRETE BARRIER | LNFT | 2,000.000 | 32.000 | 64,000.00 |
| 635(13) | MOVING TEMPORARY CONCRETE BARRIER | LNFT | 750.000 | 10.000 | 7,500.00 |
| 635(14A) | WARNING LIGHT, TYPE A | EACH | 10.000 | 200.000 | 2,000.00 |
| 635(14C) | WARNING LIGHT, TYPE C | EACH | 90.000 | 200.000 | 18,000.00 |
| 635(16) | FLASHING ARROW BOARD | HOURL | 300.000 | 10.000 | 3,000.00 |
| 635(17) | TEMPORARY TRAFFIC MARKING | LNFT | 6,000.000 | 0.500 | 3,000.00 |
| 635(20) | FLAGGER | HOURL | 100.000 | 12.000 | 1,200.00 |
| 635(27) | IMPACT ATTENUATOR | EACH | 1.000 | 2,000.000 | 2,000.00 |
| 637(3) | COMBINED FIELD OFFICE AND FIELD LABORATORY | EACH | 1.000 | 14,000.000 | 14,000.00 |
| | | | | \$ | 800,000.00 |

SMALL BUSINESS CONCERN:
 SMALL DISADVANTAGED BUSINESS CONCERN:
 WOMAN-OWNED BUSINESS:
 TYPE OF BID GUARANTEE:
 BID CONSIDERED RESPONSIVE:

BIDS OPENED BY:
 BIDS READ BY:

CERTIFIED COMPLETE AND ACCURATE

 DAVID O. WEBER
 ENGINEERING COORDINATOR